BRUHATH BENGALURU MAHANAGARA PALIKE

No. EE/WEST/TEND/04/2023-24

Office of the Executive Engineer
Road Infrastructure-West,
PalikeSoudha, 14th cross, 1st Stage
Chandra Layout, Bangaluru-560039,
Dated: 15.02.2024

Corrigendum & Proceedings of Pre-bid meeting

Name of work: "Comprehensive Development of Footpath & White topping for 8 Major Roads in BBMP West Zone Limit under Package-3"

Reference: 1.This office Tender Notification No: EE/WEST/TEND/04/2023-24, Dated: 08.02.2024
2. M/s Jathin Infra Pvt Ltd, dated:15.02.2024

BBMP officers present:

1. Sri.Prahallad B.S., Engineer-In-Chief, BBMP
2. Sri.Devraj.V, Executive Engineer, Road Infrastructure-West.
3. Mrs.Deepthi Priya. Assistant Engineer, Road Infrastructure-West.

Bidders

1. M/s JIPL, represented by Sri.Shivaram

****

The meeting was commenced as per the scheduled time and the bidders were welcomed for the meeting. The following query was submitted and was clarified which were as follows:

Sl No	Tender Condition	Queries	Replies
1.	No No.5 of IFT Table Period Completion 11 Months (including monsoon)	Due to delay will be happen to obtain permission from Traffic Police for closing of Road for White Topping and shifting of BWSSB, UGD line & water supply pipe line etc to complete the work within 11 months (including monsoon) is highly impossible. So, please change period of completion to 24 Months (including monsoon).	Tender conditions published prevail without any changes.

2.	Section 5: CONDITIONS CONTRACT of D. Cost Control No 40 Price Adjustment: Not applicable	To complete the work within the 11 months (including monsoon) is highly impossible due to above reasons. Hence, we kindly request to add the Price Adjustment clause for All Commodities, Machinery, Labour, Cement, Steel, Bitumen and Fuel to the contractor based on the all India average wholesale price index.	Since the tender is floated for 11 months period, the tender conditions prevails without any changes.

Other discussions :

As per the discussions held in the Pre-bid meeting following points are incorporated in the Tender document.

Sl. No	Reference of bidding document	Clause No	Clarification
1	Tender document	Addition to Special Condition of Contract under SECTION F of Clause No.~~40~~ 51	The rates for laying of White Topping are adopted for using SLIP FORM PAVER. Due to technical reasons /Site conditions, if FIXED FORM PAVER is used then Rs.259.60/Cum along with +/- Tender Operating Premium will be deducted from the quoted rates.
2	Tender document	Addition to Special Condition of Contract under SECTION F of Clause No.50	The Maintenance of the Roads handed over to the Contractor for White Topping is the sole responsibility of the Contractor. He shall ensure that the Pavement Layers are maintained in the Motorable Conditions without any Potholes from the Day of Issue of Notice to proceed with the Work. If the Contractor fails to maintain the Road, the Contractor will be liable to pay Penalty of Rs. 10,000/- per pothole per day for each day of Delay from the Date of Notice issued to the Contractor in this regard and in addition the Employer shall be at liberty to make arrangement and provide facilities as aforesaid and recover the cost from the contractor.

3	Tender document	Earnest Money Deposit and Security Deposit	The e-bank guarantee submission towards Earnest Money Deposit and Security Deposit can be changed to e-bank guarantee/FDR/BG.
4	Tender document	Mobilization Advance	The e-bank guarantee submission towards Mobilization Advance can be changed to e-bank guarantee/FDR/BG.
5	Tender document	Special Condition of Contract-Clause F, No.44- Concrete	The Contractor shall obtain Pavement Quality Concrete only from the Ready Mix Concrete (RMC) Plants established from Reputed Cement Manufacturers can be changed to The Contractor shall obtain Pavement Quality Concrete only from the Ready Mix Concrete (RMC) Plants established from M/.s Ultratech Cemnent or Reputed Cement Manufacturers.
6.	Tender document	IFT Sl. No. (5) GST shall be paid to the tendered amount separately.	Since GST is included in the Amount put to tender, this clause is 'Deleted'.

16/2/24

Executive Engineer
RI-West Division

Engineer in Chief
Bruhat Bengaluru Mahanagara Palike